










$\theta = 0.0^\circ$; $\psi = 0.0^\circ$; $V = 0.000$ m/s (0 r/min)

Estimated measurement uncertainties of natural convection at $\theta = 0.0$.


Symbol	Nominal	Sensitivity	Bias	Uncertainty	Component
ΔT	25.0.K	+4.43%/K	0.10.K	0.44%	LM35C differential
P	101.kPa	+0.0002%/Pa	1.5.kPa	0.29%	MPXH6115A6U air pressure
Re_0	600	+0.0049%	60	0.30%	integration lower-bound
D_o	2.81.mm	+3780%/m	500.um	1.89%	tube outer diameter
D_i	1.11.mm	+3989%/m	200.um	0.80%	tube inner diameter
L_{wire}	38.0.mm	+941%/m	500.um	0.47%	wire length
k_{ABS}	179. $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	+0.117%/ $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	9.0. $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	1.05%	ABS thermal conductivity
d	12.0.mm	+5121%/m	100.um	0.51%	disk diameter
θ	50.0.m°	+3.52%/°	0.20.°	0.70%	plate angle
				2.59%	combined bias uncertainty



$\theta = 0.0^\circ$; $\psi = 0.0^\circ$; $V = 0.194$ m/s (64 r/min)

Estimated measurement uncertainties at $Re = 141$.


Symbol	Nominal	Sensitivity	Bias	Uncertainty	Component
ΔT	25.0.K	+4.02%/K	0.10.K	0.40%	LM35C differential
P	101.kPa	+0.0003%/Pa	1.5.kPa	0.50%	MPXH6115A6U air pressure
η	0.340	+99.6%	0.007	0.68%	anemometer calibration
D_i	1.11.mm	+4902%/m	200.um	0.98%	tube inner diameter
D_g	166.um	-276%/m	750.um	0.21%	tube air gap
L_{wire}	38.0.mm	+1150%/m	500.um	0.57%	wire length
k_{ABS}	179. $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	+0.138%/ $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	9.0. $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	1.23%	ABS thermal conductivity
d	12.0.mm	+5135%/m	100.um	0.51%	disk diameter
θ	50.0.m°	-1.33%/°	0.20.°	0.27%	plate angle
				2.02%	combined bias uncertainty
Symbol	Nominal	Sensitivity	Variability	Uncertainty	Component
ω	64.3.r/min	+0.527%/(r/min)	1.1.r/min	0.60%	fan rotation rate
				2.35%	RSS combined uncertainty



$\theta = 0.0^\circ$; $\psi = 0.0^\circ$; $V = 0.380$ m/s (126 r/min)

Estimated measurement uncertainties at $Re = 277$.


Symbol	Nominal	Sensitivity	Bias	Uncertainty	Component
ΔT	25.0.K	+3.95%/K	0.10.K	0.39%	LM35C differential
P	101.kPa	+0.0002%/Pa	1.5.kPa	0.32%	MPXH6115A6U air pressure
η	0.340	+74.1%	0.007	0.50%	anemometer calibration
Re_0	600	-0.0037%	60	0.22%	integration lower-bound
C_B	0.541	+2.73%	0.100	0.27%	bypass coefficient
D_o	2.81.mm	-7036%/m	500.um	3.52%	tube outer diameter
D_i	1.11.mm	+6614%/m	200.um	1.32%	tube inner diameter
D_g	166.um	-327%/m	750.um	0.25%	tube air gap
L_{wire}	38.0.mm	+1365%/m	500.um	0.68%	wire length
k_{ABS}	179. $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	+0.141%/ $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	9.0. $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	1.26%	ABS thermal conductivity
d	12.0.mm	+5561%/m	100.um	0.56%	disk diameter
				4.15%	combined bias uncertainty
Symbol	Nominal	Sensitivity	Variability	Uncertainty	Component
ω	126.r/min	+0.199%/(r/min)	1.1.r/min	0.22%	fan rotation rate
				4.17%	RSS combined uncertainty



$\theta = 0.0^\circ$; $\psi = 0.0^\circ$; $V = 0.748 \text{ m/s}$ (250 r/min)

Estimated measurement uncertainties at $Re = 546$.


Symbol	Nominal	Sensitivity	Bias	Uncertainty	Component
ΔT	25.0.K	+3.96%/K	0.10.K	0.40%	LM35C differential
P	101.kPa	+0.0005%/Pa	1.5.kPa	0.74%	MPXH6115A6U air pressure
η	0.340	+154%	0.007	1.05%	anemometer calibration
Re_0	600	-0.0047%	60	0.28%	integration lower-bound
C_B	0.541	+4.70%	0.100	0.47%	bypass coefficient
D_o	2.81.mm	+987%/m	500.um	0.49%	tube outer diameter
D_i	1.11.mm	+9297%/m	200.um	1.86%	tube inner diameter
D_g	166.um	-415%/m	750.um	0.31%	tube air gap
L_{wire}	38.0.mm	+1729%/m	500.um	0.86%	wire length
k_{ABS}	179. $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	+0.150%/ $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	9.0. $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	1.34%	ABS thermal conductivity
d	12.0.mm	+5900%/m	100.um	0.59%	disk diameter
				2.97%	combined bias uncertainty
Symbol	Nominal	Sensitivity	Variability	Uncertainty	Component
ω	250.r/min	+0.210%/(r/min)	1.0.r/min	0.22%	fan rotation rate
				3.00%	RSS combined uncertainty



$\theta = 0.0^\circ$; $\psi = 0.0^\circ$; $V = 1.466 \text{ m/s}$ (500 r/min)

Estimated measurement uncertainties at $Re = 1070$.


Symbol	Nominal	Sensitivity	Bias	Uncertainty	Component
ΔT	25.0.K	+3.95%/K	0.10.K	0.39%	LM35C differential
P	101.kPa	+0.0004%/Pa	1.5.kPa	0.61%	MPXH6115A6U air pressure
η	0.340	+126%	0.007	0.86%	anemometer calibration
Re_0	600	-0.0077%	60	0.46%	integration lower-bound
C_B	0.541	+6.76%	0.100	0.68%	bypass coefficient
D_o	2.81.mm	-4711%/m	500.um	2.36%	tube outer diameter
D_i	1.11.mm	+11798%/m	200.um	2.36%	tube inner diameter
D_g	166.um	-495%/m	750.um	0.37%	tube air gap
L_{wire}	38.0.mm	+2063%/m	500.um	1.03%	wire length
k_{ABS}	179. $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	+0.154%/ $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	9.0. $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	1.38%	ABS thermal conductivity
d	12.0.mm	+6601%/m	100.um	0.66%	disk diameter
				4.08%	combined bias uncertainty
Symbol	Nominal	Sensitivity	Variability	Uncertainty	Component
ω	500.r/min	+0.086%/(r/min)	1.4.r/min	0.12%	fan rotation rate
				4.08%	RSS combined uncertainty



$\theta = 0.0^\circ$; $\psi = 0.0^\circ$; $V = 2.131 \text{ m/s}$ (750 r/min)

Estimated measurement uncertainties at $Re = 1555$.

Symbol	Nominal	Sensitivity	Bias	Uncertainty	Component
ΔT	25.0.K	+3.95%/K	0.10.K	0.39%	LM35C differential
P	101.kPa	+0.0004%/Pa	1.5.kPa	0.63%	MPXH6115A6U air pressure
η	0.340	+122%	0.007	0.83%	anemometer calibration
Re_0	600	-0.0084%	60	0.50%	integration lower-bound
C_B	0.541	+7.83%	0.100	0.78%	bypass coefficient
D_o	2.81.mm	-5337%/m	500.um	2.67%	tube outer diameter
D_i	1.11.mm	+12273%/m	200.um	2.45%	tube inner diameter
D_g	166.um	-513%/m	750.um	0.38%	tube air gap
L_{wire}	38.0.mm	+2136%/m	500.um	1.07%	wire length
k_{ABS}	179. $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	+0.150%/ $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	9.0. $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	1.34%	ABS thermal conductivity
d	12.0.mm	+7142%/m	100.um	0.71%	disk diameter
				4.34%	combined bias uncertainty
Symbol	Nominal	Sensitivity	Variability	Uncertainty	Component
ω	750.r/min	+0.055%/(r/min)	0.82.r/min	0.05%	fan rotation rate
				4.34%	RSS combined uncertainty



$\theta = 0.0^\circ$; $\psi = 0.0^\circ$; $V = 2.724 \text{ m/s}$ (999 r/min)

Estimated measurement uncertainties at $Re = 1988$.

Symbol	Nominal	Sensitivity	Bias	Uncertainty	Component
ΔT	25.0.K	+3.95%/K	0.10.K	0.40%	LM35C differential
P	101.kPa	+0.0004%/Pa	1.5.kPa	0.64%	MPXH6115A6U air pressure
η	0.340	+113%	0.007	0.77%	anemometer calibration
Re_0	600	-0.0084%	60	0.50%	integration lower-bound
C_B	0.541	+8.51%	0.100	0.85%	bypass coefficient
D_o	2.81.mm	-5583%/m	500.um	2.79%	tube outer diameter
D_i	1.11.mm	+12412%/m	200.um	2.48%	tube inner diameter
D_g	166.um	-520%/m	750.um	0.39%	tube air gap
L_{wire}	38.0.mm	+2168%/m	500.um	1.08%	wire length
k_{ABS}	179. $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	+0.146%/ $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	9.0. $\frac{\text{mW}}{\text{K}\cdot\text{m}}$	1.31%	ABS thermal conductivity
d	12.0.mm	+7497%/m	100.um	0.75%	disk diameter
				4.44%	combined bias uncertainty
Symbol	Nominal	Sensitivity	Variability	Uncertainty	Component
ω	999.r/min	+0.039%/(r/min)	1.8.r/min	0.07%	fan rotation rate
				4.44%	RSS combined uncertainty